

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the Work : Improvements of Roads and Drains in Amruthahalli in S.C Colony in 1st and 3rd cross Ward no 07 Byatarayanapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	549.76	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications	cum	75.60	
2	932.00	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occurring during rolling including cost of all labour, HOM of machinery complete as per specifications. (P. 145, I.No. 19.64) SR-2014-15	cum	4.482	
3	186.40	KSRRB 300-64.2. Extra for watering the earth to bring the earth upto required optimum moisture content with machinery including cost of all labour, HOM of machineries complete as per specifications. (P. 146, I.No. 19.72) SR-2014-15	Cum	2.16	
4	247.80	KSRRB 4-1.3 Providing and laying cement concrete using 40mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exclusive of cost of steel, fabrication and plastering charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-341 Kg/cum) (P. 12, I.No. 4.3) SR-2014-15	Cum	4847.04	
5	173.20	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exclusive of cost of steel, fabrication and plastering charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (P. 18, I.No. 4.49.1) SR-2014-15	Cum	5847.12	
6	932.00	Vacuum de-watering with vacuum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift. (P. 171 I. No. 22.7) SR-2014-15	Sqm	97.20	


M. S. (M. S.)

7	80.00	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. for concrete pavement(P. 172 I. No. 22.8.1) SR-2014-15	Rmtr	124.20	
8	6.40	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P. 17, I.No. 4.46) SR-2014-15	qtl	78351.84	
9	480.00	KSRB 15.1.3 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.109.I.No. 15.3) SR-2014-15	Sqm	92.88	
10	549.76	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 5.00 Km (Page No.141)	Cum	81.00	


 Chief Engineer
 Yelahanka Zone
 Bangalore Mahanagara Pr
 92
 ಶರಣ ಬೆಂಕರ್ ಪಟ್ಟಣ
 ಅಧ್ಯಕ್ಷರ ಸಹಾಯಕಿ (N/L)
 ಅಧ್ಯಕ್ಷರ ಕಛೇರಿ/ಅಧಿಕಾರಿ
 ಅನುಮೋದನೆ ನೀಡಿರುವುದು


 Executive Engineer
 Byatarayanapura Division
 BBMP, Bangalore - 92

